



SUNSHINE COAST REGIONAL DISTRICT

ADDENDUM NO. # 3

Invitation to Tender No. 18 368

Chapman Creek Bridge Watermain Replacement

Date: January 21, 2019

This addendum forms part of the contract documents and shall be read, interpreted, and coordinated with all other parts. The costs of all work contained herein shall be included in the tender submission. The following revisions, clarifications, changes, additions, or deletions supersede the information contained in the original documents to the extent referenced and shall become part thereof:

Number of pages including attachments: (2 pages)

Item No.1

Addendum # 3 contains a question received which resulted in the issuing of a revised schedule of quantities.

Question 1

I am just looking for clarification on payment items 4 and 5. Will payment item 5 (pre-insulated watermain) extend to the outside of the bridge abutments? Will payment item 4 (buried watermain) be from the outside of the bridge abutments to the cut ductile iron pipe or only to the HDPE flange adapter?

Answer:

The distances shown are to where the existing DI pipe is cut. The pre-insulated pipe unit price extends to the outside of the bridge abutments, although the insulation stops 150 mm before the bridge abutments. The buried pipe unit price extends to the flange adapter on the existing DI pipe. However, it is noted that the quantities in the tender are slightly higher than what is actually to be installed. The 38 m of pre-insulated pipe should be 35 m and the 8 m of buried pipe should be 5 m. Attached is a revised Appendix 1 Schedule of Quantities and Pricing.

Addendum No. # 3 is issued prior to receipt of submission and shall form part of the contract documents. The revisions shall clarify the information contained in the original Proposal documents issued on December 13, 2018.

If you have any questions regarding the above, please contact the undersigned.

Gordon Rischaneck - Purchasing Officer
Sunshine Coast Regional District